

**PUBLIC OPENING - Friday 10 May 2019 at 10.40 hrs.**

**Resurfacing of Road for period ending 31 December 2019 – DCGP/RBD/W002/2019**

Item No	Brief Description of Works	Unit of Measure	Rate <u>Incl of VAT</u> (Rs)	Rate <u>Incl of VAT</u> (Rs)
			TRANSINVEST	MONESH ENTERPRISES CO. LTD
1	Supply and lay bituminous concrete wearing course (0/10) 40 mm thick with binder content 6%. The price quoted shall handle: - Preparatory works on the road being resurfaced, which shall include sweeping, carting away of all materials to be disposed of. - Cut and patch with bituminous concrete 0/14 including spaying of bitumen binder as tack coat - The cross fall of the road surface is to be towards the existing drain where same is existing or as directed by the Engineer. - Spraying of tack coat at the rate of 0.6 kg/m <sup>2</sup> as per specification. - Spraying, compacting and smoothing the asphalt concrete as per specification. - Rate to include for two cores to be taken as directed by the Engineer along each resurfaced road.	M <sup>2</sup>	632.50	1025
2	Manhole raising for size of chamber less or equal to 500 mm. The price quoted shall include: <b>(PROVISIONAL)</b> - Excavation in any type of materials. - Demolition of any head work or supporting slabs or re-waving the outer edge of the existing manhole. - Supply and placing of reinforced concrete, curing of concrete - Placing and adjusting the manhole covers. - Trimming of the edges and clearing of site.	No	5707.45	125
3	Manhole raising for size of chamber, which are greater than 500 mm. The price quoted shall include: <b>(PROVISIONAL)</b> - Excavation in any type of materials. - Demolition of any head work or supporting slabs or re-waving the outer edge of the existing manhole. - Supply and placing of reinforced concrete, curing of concrete - Placing and adjusting the manhole covers. - Trimming of the edges and clearing of site.	No	5707.45	150
4	Road marking with white thermo plastic paint. Rate to include for survey of road marking, clearing and marking out and supply of appropriate traffic signs. <b>(PROVISIONAL)</b>	M <sup>2</sup>	691.15	25

**PUBLIC OPENING - Friday 10 May 2019 at 10.40 hrs.**

**Renovation of Kiosk and Jetty at Mahebourg Waterfront – DCGP/RBD/W003/2019**

<i>Item</i>	<i>Description</i>	<i>Amount Rs</i>	<i>Amount Rs</i>	<i>Amount Rs</i>	<i>Amount Rs</i>	<i>Amount Rs</i>
		<b>Anil Puttoo Building and Civil Contracting Co. Ltd</b>	<b>T.K Construction Ltd</b>	<b>Garage Barlen</b>	<b>Prakash Foolchund Co. Ltd</b>	<b>Island Civil Mechanical Contracting Ltd</b>
1	Remove all existing metal sheets and associated accessories on kiosk and cart away	50,000	25,000	20,000	30,000	900,000
2	Clean and treat all wooden beams and purlins to satisfaction of the Project Manager The existing wooden parts should be cleaned by means of mechanical sanding or other means. All gaps, holes etc should be filled with wood putty and leveled to even surface	50,000	75,000	78,000	50,000	500,000
3	Apply two coats each of sealer, primer, under coat and gloss paint to all wooden parts to the satisfaction of the Project Manager. Additional coats should be applied to get a uniform appearance. Colour to be similar as existing.	60,000	150,000		50,000	250,000
4	Supply and fix new profile rib sheets type "Zinc Alu" of min thickness 0.63 mm and having a minimum zinc coating of 150 g/m2. Sample, colour and product specification from supplier, shall be approved by the Project Manager prior to purchase. Price to include all cutting, placing, sealant strips, fixations etc as per manufacturer's recommendation.	250,000	250,000	130,000	150,000	1,000,000

5	Supply and fix flashing (hot dipped galvanized, min thickness similar as profile sheets and size 150 x 150 mm) metal sheets bent to shape and fixed to purlin on all edges and joints. Flashband or equivalent to be laid prior to fixing of flashing.	50,000	25,000	35,000	150,000	500,000
6	To remove all damaged wooden planks along the floor of jetty and kiosk and cart away To remove uneven wooden planks along the floor of jetty and kiosk Supply and place new wooden planks meranti (treated for outdoor use) of width approx 150mmx 40 mm thick along jetty and flooring of kiosk. Length to be adjusted to match existing alignment.	75,000	100,000	103,000	175,000	2,000,000
7	To supply and fix wooden meranti planks (100mm x37mm) along both sides of jetty and kiosk for clamping of the existing wooden floor planks to prevent loosening of planks already bolted Fixation details to be provided by contractor for approval. Inox type or anti rust type fittings to be used. All other damaged bolts, screws or other fittings such as washers etc should be removed and same replaced by screws or bolts of inox type or anti rust type All samples to be approved by Project Manager	75,000	80,000	79,000	180,000	2,000,000
8	To supply and replace all damaged rope along both sides of the jetty and around kiosk. Material to be of similar or near similar size and type. Existing guardrails and posts should be cleaned and painted. The wooden posts and parts should be cleaned by means of mechanical sanding or other means. All gaps, holes etc should be filled with wood putty to give an even surface Works to include removal of rust layer to metal parts,	50,000	75,000	39,000	175,000	1,500,000

	primer application and paint application of minimum two coats. Sample of rope to be approved by Project Manager.					
9	<b><u>Provisional Items:</u></b> The existing metal substructure of the jetty and kiosk should be cleaned and treated. Metal parts should be treated by first removing rusty layer and scaling. Paint primer (galva primer PA 10 or equivalent) to be applied minimum two coats and gloss paint minimum two coats should be applied. Methodology and materials used should be approved by Project Manager prior to start of work. Methodology should include the use of support and props as well as sea water diversion and/or prevention of water to working area.	60,000	1,000,000	800,000	75,000	500,000
<b>Subtotal</b>		720,000	1,780,000	1,284,000	1,035,000	9,150,000
<b>VAT @ 15%</b>		108,000	267,000	Nil	155,250	1,372,500
<b>TOTAL (RS)</b>		<b>828,000</b>	<b>2,047,000</b>	<b>1,284,000</b>	<b>1,190,250</b>	<b>10,522,500</b>