

**PUBLIC OPENING – THURSDAY 04 JULY 2019 AT 10.40 HRS**

**UPGRADING OF FENCING AT PLAINE MAGNIEN FOOTBALL GROUND - DCGP/RBD/W004(i)/2019**

<i>Item No.</i>	<i>Description</i>	<i>Unit</i>	<i>Qty</i>	<i>Amount (Rs) First Grade Construction Ltd</i>	<i>Amount Rs Garage Barlen Co. Ltd</i>	<i>Amount Rs Mumtaz Enterprise Ltd</i>	<i>Amount Rs Island Civil &amp; Mechanical Contracting Ltd</i>	<i>Amount Rs REK Security, Construction &amp; Cleaning Co. Ltd</i>	<i>Amount Rs Vardhini &amp; Co. Ltd</i>	<i>Amount Rs Team Builders Co Ltd</i>
1	<p><u>Site Clearance</u></p> <ul style="list-style-type: none"> <li>Remove existing chain link fencing on side A as per drawing (approx 140 meters) and return to DC yard.</li> <li>Carefully cut and remove all metal poles and return to the store of District council of Grand Port.</li> <li>Remove all associated existing blockwall, concrete columns, bases etc and cart away of all debris.</li> <li>Demolish all concrete benches on side A as per drawing and cart away all debris.</li> </ul>	Sum		50,000	95,000	400,000	200,000	10,000	110,000	95,000
								10,000		

2	<p><u>Construction of fencing with low wall as per drawings and specifications</u>  Price to include the following but not limited to:</p> <ul style="list-style-type: none"> <li>• Setting out</li> <li>• Excavation</li> <li>• Concrete blinding</li> <li>• Bases</li> <li>• Blockwork</li> <li>• Columns</li> <li>• Backfilling and compaction</li> <li>• Disposal of any surplus excavated material as directed on site</li> <li>• Coping layer</li> <li>• Fencing complete with poles &amp; straining wires</li> <li>• All welded parts to be treated with 2 coats galvafruid, one coat primer, two coats aluminium paint.</li> <li>• Internal face: Render 10mm final thickness using cement and sand (1:3) mixed with an approved plasticiser. All copings and columns to be sponged finished. Blockwork panel to be tyrolean rendered with same texture as existing. Rate to include</li> </ul>	m	<b>140</b>	1,190,000	1,100,400	1,700,000	1,680,000	5,000 35,000 20,000 90,000 193,000 75,000 20,000  40,000  50,000 332,000  15,000  80,000	525,000	1,180,000
---	---	---	------------	-----------	-----------	-----------	-----------	---	---------	-----------

	<p>for hacking of concrete and labour for forming arises and fair edges.</p> <ul style="list-style-type: none"> <li>External face: Render 10mm final thickness using cement and sand (1:3) mixed with an approved plasticiser. All copings and columns to be sponged finished. Blockwork panel to be sponged finished. Rate to include for hacking of concrete and labour for forming arises and fair edges.</li> <li>Price to include for reinstatement of turfing where excavation and damage has been done. Prepare ground by removing weeds, stones and large lumps 50mm and above. Supply, spread and lightly compact top soil where required to a minimum thickness of 300mm. Treat with appropriate herbicides, manure, compost, fertilizer and the like. Supply and place grass 'chien dent' type at 150mm intervals.</li> </ul>							75,000		
								10,000		
3	<p><u>Pedestrian Gate</u></p> <ul style="list-style-type: none"> <li>Supply and place</li> </ul>	no	1	35,000						

