

PUBLIC OPENING – 25 JUNE 2019 AT 10.45 HRS

Extension and Covering of Bleaches at Quatre Soeurs Football Ground - Ref No: DCGP/RBD/W005/2019

Item No.	Description	Unit	Qty	Garage Barlen Co. Ltd	T.K. Construction Ltd	Mumtaz Enterprise Ltd	Team Builders Co. Ltd	Furnicon Ltd	Island Civil and Mechanical Contracting Ltd	Vardhini & Co. Ltd
1	<p><u>Site Clearance, Demolition and Signage</u></p> <ul style="list-style-type: none"> Demolition of existing boundary wall as per drawing, including removal of petangue court without disturbing the adjacent structures and carting away all debris. Dismantling of existing children equipment and return to store at the District council of Grand Port as indicated on site. Clearing the site of all shrubs, bushes and carting away Supply and place signboard as per drawing. <p>Care should be taken so as not to damage the existing fenced meteorological structure.</p>	Sum		111,000	50,000	400,000	175,000	290,000	200,000	79,000
2	<p><u>Construction of concrete bleachers as per drawings and specifications</u></p> <p>Price to include the following but not limited to:</p> <ul style="list-style-type: none"> Setting out 	Sum		730,000	890,000	515,000	400,000	869,000	2,000,000	595,000

<ul style="list-style-type: none"> • Excavation • Strip footings (reinforcement, formwork and concreting) • Bases (reinforcement, formwork and concreting) • Blockwork (reinforcement, formwork and concreting) • Columns (reinforcement, formwork and concreting) • Ground beam (reinforcement, formwork and concreting) • Backfilling and compaction • Disposal of any surplus excavated material as directed on site • Flooring(reinforcement, formwork and concreting) • Joints as per drawings • Render all exposed surfaces using 10 mm thick smooth rendered cement and sand (1:3) mixed with an approved plasticiser on concrete and blockwork surfaces. Rate to include for hacking of concrete and labour for forming arises and fair edges. <p>Testing of materials as per specifications.</p>									
--	--	--	--	--	--	--	--	--	--

3	<p><u>Construction of fencing with low wall as per drawing and specifications</u></p> <p>Price to include the following but not limited to:</p> <ul style="list-style-type: none"> • Setting out • Blockwork • Columns • Disposal of any surplus excavated material as directed on site • Coping layer • Fencing complete with poles & straining wires • Render internally, externally and all exposed surfaces using 10 mm thick sponge rendered cement and sand (1:3) mixed with an approved plasticiser on concrete and blockwork surfaces. Rate to include for hacking of concrete and labour for forming arises and fair edges. • Painting of parapet wall (inclusive of coping) internally and externally using one coat undercoat/binder and two coats of anti fungus paint. Colour to be approved by project manager. <p>Price to include for surface preparation (cleaning, filling with crack filler, sanding etc) Contractor may be requested to paint into more than 1 color.</p>	Sum		418,000	100,000	540,000	185,000	1,462,500	700,000	293,000
---	---	-----	--	---------	---------	---------	---------	-----------	---------	---------

4	<p><u>Pedestrian Gate</u></p> <ul style="list-style-type: none"> Supply and place pedestrian gate as per drawings and specifications. Price to include for labour, materials, locks, and associated works. <p>Location of gate will be shown on site</p>	Sum		26,000	10,000	6,000	17,000	15,000	50,000	17,000
5	<p><u>Construction of CIS Structure as per drawings</u></p> <p>Supply and place CIS structure as per drawing and specification. Price to include the following but not limited to:</p> <ul style="list-style-type: none"> Setting out Concrete bases Metal works CIS sheeting. Colour of CIS to be approved by the project manager Rainwater gutter Rainwater pipes (3 nos per bleachers) Painting Works <p>All welded parts to be treated with 2 coats galvafruid.</p> <p>Painting of the metal sections using 2 coats of self etching primer and 2 coats of gloss paint. Colour of paint to be approved by</p>	Sum		820,000	1,050,000	650,000	1,190,000	325,000	1,000,000	267,000

	project manager All samples of fitting and fixation to be approved by the project manager.									
6	<u>Handrails (PROVISIONAL)</u> Supply and place handrails as per drawings and specification	Sum		159,000	125,000	96,000	50,000	110,000	100,000	117,000
7	<u>Pathway/Soakaway (PROVISIONAL)</u> Construction of pathway over full length of bleachers. To consist of 500mm thick spalls 100-150mm, 50mm thick gravels 50-75mm and 50mm aggregates 25mm & 16mm	Sum		21,000	75,000	250,000	25,000	175,000	200,000	93,000
	Sub Total 1			2,285,000	2,300,000	2,457,000	2,042,000	3,246,500	4,250,000	1,461,000
	Contingency			50,000.00	50,000.00	50,000.00	50,000.00	50,000.00	50,000.00	50,000.00
	Sub Total 2			2,335,000	2,350,000	2,507,000	2,092,000	3,296,500	4,300,000	1,511,000
	VAT 15%			nil	352,000	376,050	306,300	494,475	645,000	226,650
	TOTAL			2,335,000	2,702,000	2,883,050	2,398,300	3,790,975	4,945,000	1,737,650