

**THE DISRICT COUNCIL OF GRAND PORT**

**PUBLIC OPENING – 04 SEPTEMBER 2019 AT 10.40 HRS**

**Supply, fixing and commissioning of a new lighting system at the Grand Bel Air football ground**

Procurement Reference Number: *DCGP/RBD/W007/2019*

<i>Item No</i>	<i>Brief Description of Works:</i>	<i>Qty</i>	<i>Rates Rs</i>	<i>Amount Rs</i>	<i>AmountRs</i>	<i>AmountRs</i>	<i>AmountRs</i>	<i>AmountRs</i>
				M&E Ltd	Mauritech Limited	LumitechLtee	Magnet Energise Ltd	Kabelek Engineering Ltd
1.0	<b>OCTAGONAL POLES</b> The council shall award either item 1.1 or 1.2.							
1.1	Supply and place 6 nos octagonal hot dipped galvanized metal pole, <b>as per drawings</b> , with all necessary accessories (brackets/cross arm to receive floodlights, bolts, base plates, anchor bolts etc.). Work to be carried out in accordance as per health and safety norms and using crane lorry. Price to include for setting out and placing of anchor bolts and securing same to levels and positions prior to casting of concrete bases.  <i>NOTE: Excavation and casting of bases shall be done by civil works' contractor and SHALL NOT BE QUOTED. Exact positions of bases shall be confirmed on site.</i> However adequate supervision shall be done to prevent any deviation from the contract. Care to be taken not to damage turfing outside the	Sum						

	working area.							
1.2	<p>Supply and fix octagonal hot dipped galvanised metal pole, <i>as per contractor's proposal</i>, with all necessary accessories (brackets/cross arm to receive floodlights, bolts, base plates, anchor bolts etc.). Work to be carried out in accordance as per health and safety norms and using crane lorry.</p> <p>Proposal to be accompanied by:</p> <ul style="list-style-type: none"> <li>• A design calculation report, considering design wind speeds of 300 km/hr, vetted by a civil engineer registered under the Registered Professional Engineers Council Act and having at least 3 years post registration experience in at least 2 similar projects over the last 3 years.</li> <li>• Drawings of proposal made with all details (base plates, bolts, cross arms etc)</li> </ul> <p>Price to include for setting out and placing of anchor bolts and securing same to levels and positions prior to casting of concrete bases.</p> <p><b>NOTE: Excavation and casting of bases shall be done by civil works' contractor and SHALL NOT BE QUOTED. Exact positions of bases shall be confirmed on site.</b> However adequate supervision shall be done to prevent any deviation from the contract.</p> <p>Care to be taken not to damage turfing outside the working area.</p>	Sum						

<b>2.0</b>	<b>FLOODLIGHT (Metal halide)</b>							
2.1	<p>Supply and fix 18 nos1000w floodlights as per specifications. 3 floodlights to be placed per pole and properly oriented to avoid any blackspot. For each pole, price to include for:</p> <ul style="list-style-type: none"> <li>• Supply and fixing of flexible cables 2.5 mm<sup>2</sup> 3 core for each floodlight and connected to individual very high quality breakers 32A double pole (3 nos per pole) easily accessible from access door.</li> <li>• Supply and fixing of flexible cables 2.5 mm<sup>2</sup> 3 core from each individual breakers 32A double pole to a 3 Phase breaker 40A 4 poles easily accessible from access door.</li> <li>• Individual earthing system for each pole and associated floodlight</li> <li>• More or less equal load balancing to be done among the 3 Phases</li> </ul> <p>Sample of breaker and floodlight to be submitted for approval by the project manager prior to purchase and placing.</p>	Sum						
<b>3.0</b>	<b>CABLES IN TRENCH</b>							
3.1	<p>Supply and place electrical conduit or PVC high pressure type pipes into trench as per drawings. Exact alignment of trench shall be confirmed on site. Supply, lay and connect very high quality armoured copper cables 6 mm<sup>2</sup> 4 core in trenches from 3 Phase breaker 40A 4 poles in each pole to breakers in distribution panel. Sample of cabling to be submitted for approval by the project manager prior to purchase and placing. Certificate to certify compliance to MS101 may be requested by the project manager. No connections or electrical wire joint shall be made in</p>	SUM						

	the cables from poles to main distribution board and lengths of cables shall be inspected by the project manager or his representative prior to laying in sleeves/pipes. <b>NOTE: Excavation, backfilling, warning tape, warning slab and draw pits shall be done by civil works' contractor and SHALL NOT BE QUOTED.</b>							
<b>4.0</b>	<b>DISTRIBUTION PANEL</b>							
4.1	Supply and fix wall mounted distribution panel, inside the cloakroom, of approx. dimension 1400 x 590 mm, made of factory painted hot dipped galvanized steel or equivalent rust resistant material; having IP 42 or better; to be secured by lock. Works should include the supply and fixing of all wiring, electrical controls and accessories (one isolator 4 pole 100 A, RCD 4 pole 100 A, Busbars 3 phase 125 A, 6 Breakers 4 pole 40 A, 6 Contactors 40 A 3 Phase, 6 rotary switch ON/OFF for each electrical pole to be fixed outside the distribution board). Price to include for 16mm <sup>2</sup> 4 core copper from meter to main isolator, RCD and busbars; and 6 mm <sup>2</sup> 4 core from busbar to existing sub distribution panel. All exposed wiring to be concealed in trunking/sleeves where required and all joints sealed with silicon. <b>NOTE: Cabling from transformer to CEB meter shall be done by the employer and shall not be quoted for.</b>	SUM						
<b>5.0</b>	<b>SPARE PARTS (<u>Provisional</u>)</b> Supply the following spare parts:							
5.1	Floodlights 1000W as per specification	6 nos						

				<i>Amount Rs</i>	<i>Amount Rs</i>	<i>Amount Rs</i>	<i>Amount Rs</i>	<i>Amount Rs</i>
				<b>M&amp;E Ltd</b>	<b>Mauritech Limited</b>	<b>LumitechLtee</b>	<b>Magnet Energise Ltd</b>	<b>Kabelek Engineering Ltd</b>
5.2	Metal halide bulbs 1000W compliant with floodlight proposed	12nos						
5.3	Ignitor compatible with floodlight proposed	12nos						
5.4	Ballast compatible with floodlight proposed	12nos						
			Subtotal 1					
			<b>Contingency</b>	<b>100,000.00</b>	<b>100,000.00</b>	<b>100,000.00</b>	<b>100,000.00</b>	<b>100,000.00</b>
			Subtotal 2					
			<i>VAT at 15%</i>					
			<b>TOTAL</b>	<b>1,470,375</b>	<b>1,888,350</b>	<b>1,934,221.80</b>	<b>2,452,498</b>	<b>1,121,953.80</b>