



**AWARD OF PROCUREMENT CONTRACT**

**NOTICE UNDER SECTION 40(7) OF THE PUBLIC PROCUREMENT ACT**

This is to notify that, following the bidding exercise carried out by The District Council of Grand Port for the *Construction of a Mini Soccer Pitch and Parking Facilities at La Musse Road, Nouvelle France (Ref No: DCGP/ONB/W002/2023, IFB/2023/196)*, the contract has been awarded to *Best Care Ltd of Church Road, Notre Dame, Long Mountain* as follows:

<b>Serial No</b>	<b>Description</b>	<b>UNIT</b>	<b>QTY</b>	<b>Offer Rate Exc VAT Rs</b>	<b>Offer Amount Exc VAT Rs</b>
1	Felling and uprooting of trees at the mini soccer pitch area and cart away debris.	sum	1	15,000.00	15,000.00
2	Construction of fencing (inclusive of bases, columns, blockwall etc) on all sides of the soccer pitch as per drawings and specifications. Price shall include Removal of existing overgrowth, shrubs, etc. Excavation for bases as per drawings and specifications and backfilling with excavated materials. No laps to be located in the vertical poles. No pointed edges to be found on the inside of the soccer pitch. End caps to be provided on top of all vertical posts and to be sloped. Rate shall be inclusive of all cutting, bending, welding, primer coatings, and application of galvafruid over welds. Supply and fixing of hot dipped galvanised SHS 25 x 25 x 1.2 mm thick, height 1500 mm, 120 mm centre to centre on the chain link fencing over a total length of 6000mm located behind goal post on top of wall and welded to fencing horizontal bars. Rate shall be inclusive of all cutting, welding, primer coatings, painting, and application of galvafruid. Render all faces of the wall using cement sand mix 1 to 3. Top of coping to be sloped with 5mm difference towards outside of the pitch. Prepare surface and apply one coat undercoat/binder and two coats of emulsion paint anti fungus on all exposed surfaces. Colour to be approved by Project Manager.	sum	1	1,500,000.00	1,500,000.00
3	Double leaf access gate 3.0 m wide and 3.0m high clear sizes to be manufactured in galvanised metal with 20mm galvanised T-Bars welded thereon, complete with heavy duty hinges and locking devices for pad locks. Rate to be inclusive of galvanised steel sections, cutting, welding, bending, locking device, chainlink fencing, hinges, application of galvafruid, primer coatings, painting the whole gate with 2 coats gloss paint, etc, all as per drawings.	sum	1	125,000.00	125,000.00

4	<p>Removal of existing overgrowth, shrubs etc and minimum 150mm thick topsoil over the turfing area. Allow for the construction of 4catch pits with metal grating inlets, piping PVC160mm PN25, 2 absorption pits as per drawings (each of volume 30 m<sup>3</sup>, size and shape to be confirmed on site). The rate shall be all inclusive of excavation, pipe, bedding, selected fill material, metal grating, concrete, aggregates, etc, all as per drawings.</p> <p>Levelling of base course and subgrade, supply and place crusher run 0/20 &amp; 0/31.5 (min. 150mm thick) mechanically compacted and watered as required.</p> <p>Supply and Spray prime coat cut back bitumen MC 30 at the rate 1L/M• Supply, lay and compact asphalt concrete 0/6, 30mm thick (min.) with 5% bitumen content with slope as per drawings. Price to include 3 nos core test by an independent recognized laboratory.</p> <p>Supply and install Green fields synthetic turf – 5/8 gauge, 100 polyethylene monofilament, UV resistant, Dtex 11000-13800, 130microns using 100 per cent PP thoibac with fibre lock fleece, uv stabilized 164 gm/m<sup>2</sup> with a fibre glass rotary weave of min. 120gm/m<sup>2</sup>, pile height 50mm to 80mm, yarn weight min. 1000 gm/m<sup>2</sup>, with drainage holes, Colour field green and/or olive green including rubber chips (1-3mm), average 1mm size of silica sand 35mm thick to stabilise the turf, Forbo Glue and tape or any acceptable equivalent alternative( all samples and specifications to be submitted with the bid.</p> <p>(Turf warranty certificate for at least 5 years to be submitted. Condition of warranty to be agreed with Project Manager)</p> <p>Ditto as above except supply and install white synthetic turf for line markings of width 120 mm as per drawings.</p>	sum	1	1,500,000.00	1,500,000.00
5	<p>Construction of 4nos of concrete bases 800 x 800 x 1000 mm deep cast against excavated soil with Y 8 - 150 cage reinforcement both ways along all faces, position as per site instructions. Price to include all necessary formwork, reinforcement, concrete grade 25.</p> <p>Supply and fixing of 2 nos of led Lights floodlight 200W on fencing poles as per drawings (Total:8 Nos. x 200 W). Sample and specification of LED floodlight to be approved by the project manager prior to order.</p> <p>Led light life cycle to be above 30,000 hrs, body to be in die cast aluminium, to have a guarantee of 5 years</p> <p>All light points to be well oriented and as directed to cover the whole play area</p> <p>Overhead cabling (3 core 2.5 mm 2) to be placed in appropriate conduit fixed to top horizontal bar of fencing, connected to all floodlights, control panel etc.</p> <p>Cabling after panel to incorporate for safety devices such as breakers located inside the chamber.</p> <p>Construction of a closed concrete chamber for control panel, as per site instructions and requirements of the Central Electricity Board including all necessary formwork, reinforcement and concrete grade 25</p> <p>Control panel to be housed complete with all necessary accessories (i.e RCD/ISOLATOR/BREAKER, etc.).</p> <p>Control panel to be fitted with timer + contactor and all necessary fittings and accessories. Earthing to be done as appropriate</p>	sum	1	300,000.00	300,000.00

	Separate switch to be provided for each lighting post Good quality galvanised fittings, bolts and nuts and locking devices to be incorporated in the works Contractor to provide for a mobile generator for testing the whole of the lighting system. Contractor to submit written guarantee regarding availability of spare parts, light fittings, etc To liaise the CEB for installation of network including fixing of poles, conductors and transformer if required. All Associated costs to be included in bill item.				
6	Supply and plate New Gate as per drawing and specification.	sum	1	100,000.00	100,000.00
7	Supply of spalls and crusher to level existing ground so that the finished level (tarmac) of the proposed mini soccer pitch is at least 450mm above existing ground level	sum	1	75,000.00	75,000.00
8	Supply and fixing of roof netting system	sum	1	100,000.00	100,000.00
9	To provide for tarred parking spaces for 10 vehicles (250 square metres) adjacent to the Soccer pitch. Parking area to be backfilled with spall, 150 mm crusher run and minimum 40 mm of asphalt wearing course 0/6 mm with surrounding retaining wall. Finished level of parking area to be at least 450 mm above existing ground level. Exact location of same will be indicated on site after award of contract. <b>(OPTIONAL ITEM)</b>	sum	1	125,000.00	125,000.00
10	<b>Contingencies amounting to Rs 200,000.00</b>	Sum	1	200,000.00	200,000.00
				<b>Subtotal</b>	<b>4,040,000.00</b>
				VAT @ 15%	606,000.00
				<b>TOTAL</b>	<b>4,646,000.00</b>

**Mr D. Reechaye**  
*The Chief Executive*  
*The District Council of Grand Port*  
*Royal Road*  
*Rose Belle*

**September 2023**